

321.1 DESCRIPTION

This work consists of constructing one or more courses of asphalt concrete on a prepared surface.

321.2 MATERIALS

The materials and their use shall conform to Section 320.2.

321.3 CONSTRUCTION REQUIREMENTS

The construction requirements shall be as prescribed in Section 320.3 with the following modifications:

A. Thickness: The compacted thickness of each lift shall not exceed 3 inches (75 mm).

B. Density: The minimum density requirement shall be 92 percent of SD312.

321.4 METHOD OF MEASUREMENT

Measurement as prescribed in Section 320.4.

321.5 BASIS OF PAYMENT

Payment as prescribed in Section 320.5.

THIS PAGE INTENTIONALLY LEFT BLANK